


Board of County Commissioners Agenda Request



Requested Meeting Date:

Title of Item:

REGULAR AGENDA	Action Requested	:	Direction Requested
CONSENT AGENDA	Approve/Deny	Motion	Discussion Item
INFORMATION ONLY	Adopt Resolut		aft) Hold Public Hearing* e copy of hearing notice that was published
Submitted by:			Department:
Presenter (Name and Title):			Estimated Time Needed:
Summary of Issue:			
Alternatives Outions Effects	n Othoro/Commonts		
Alternatives, Options, Effects o	n Others/Comments	5.	
Recommended Action/Motion:			
Einanaial Impact			
Financial Impact: Is there a cost associated with this	•	Yes	No
What is the total cost, with tax and Is this budgeted? Yes	d snipping? \$ No	Please Expl	lain:
3	-	7-1	

CERTIFIED COPY OF RESOLUTION OF COUNTY BOARD OF AITKIN COUNTY, MINNESOTA

ADOPTED November 9, 2021

By Commissioner: 20211109-xxx

Award Contract No. 20222

WHEREAS, Contract No. 20222 is for construction of S.A.P. 001-618-005, and

WHEREAS, sealed bids were opened for this project at 2:00 p.m. on Monday, November 1, 2021 with a total of four bids received, and

WHEREAS, Redstone Construction LLC - Mora, MN was the lowest responsible bidder in the amount of \$970,990.60.

NOW THEREFORE, BE IT RESOLVED, that Redstone Construction LLC be awarded Contract 20222.

BE IT FURTHER RESOLVED, that the chairperson of the Aitkin County Board and the Aitkin County Auditor are hereby authorized and directed to enter into a contract on behalf of Aitkin County with said low bidder upon presentation of proper contract documents.

F	I١	/F	: 1	ЛF	= N	N	B	F	R	S	Р	R	F	S	F	Ν	ΙT

All Members Voting _

STATE OF MINNESOTA) COUNTY OF AITKIN)

I, Jessica Seibert, County Administrator, Aitkin County, Minnesota do hereby certify that I have compared the foregoing with the original resolution filed in the Administration Office of Aitkin County in Aitkin, Minnesota as stated in the minutes of the proceedings of said Board on the 9th Day of November 2021 and that the same is a true and correct copy of the whole thereof.

Witness my hand and seal this 9th day of November, 2021

Jessica Seibert
County Administrator

Aitkin County Contract Bid Abstract

Project Name: Bridge Replacement over Willow River on CSAH 18

Project No.: SAP 001-618-005

Contract No.: 20222

Bid Opening: November 11, 2021 at 2:00 PM

	Project: SA CSAH 18	P 001-618-005 - Bridge Replacement over Willow River on			Engineers Est	imate	Redstone Con Mora, MN	struction, LLC	-Structural Spe Hutchinson, N	nson, MN Aitkin, MN		Glenwood, MN		nc
	Item		Units	Quantity	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price
Non-Parti						1	· · · · · · · · · · · · · · · · · · ·			Ţ	•	1	1	
1		SALVAGE SIGN	EACH	7	\$125.00		\$25.00	\$175.00			\$40.00			
2		REMOVE PIPE CULVERTS	L F	69			\$10.00	\$690.00			\$12.49		\$12.00	· · · · · · · · · · · · · · · · · · ·
3		EXCAVATION - COMMON (P)	CY	281	\$9.00	\$2,529.00	\$16.00	\$4,496.00	· · · · · · · · · · · · · · · · · · ·		\$10.77		•	
4		COMMON EMBANKMENT (CV) (P)	CY	761	\$15.00	\$11,415.00		\$3,805.00			\$23.07			
5		AGGREGATE SURFACING CLASS 5 MOD	TON	638	\$28.50	\$18,183.00	\$34.00	\$21,692.00		· · · · · · · · · · · · · · · · · · ·	\$18.66		\$44.50	· · · · · · · · · · · · · · · · · · ·
6	2123.51	3.0 CU YD SHOVEL	HOUR	8	\$185.00	\$1,480.00	\$180.00	\$1,440.00			\$225.00		\$250.00	
7	2123.51		HOUR	8	\$185.00	\$1,480.00	\$170.00	\$1,360.00			\$185.00		\$200.00	
8		REMOVE EXISTING BRIDGE	LS	1	\$18,500.00	\$18,500.00	\$58,000.00	\$58,000.00			\$44,516.47		\$40,000.00	
9	2501.502	18" GS PIPE APRON	EACH	4	\$450.00	\$1,800.00	\$350.00	\$1,400.00		\$1,000.00	\$350.00		\$350.00	\$1,400.00
10		18" CS PIPE CULVERT	LF	116	\$40.00	\$4,640.00	\$65.00	\$7,540.00			\$75.47		\$65.00	
11	2511.507	RANDOM RIPRAP CLASS III	CY	14	\$60.00	\$840.00	\$110.00	\$1,540.00	\$70.00	\$980.00	\$80.00	\$1,120.00	\$88.00	\$1,232.00
12		EROSION CONTROL SUPERVISOR	LS	1	\$2,500.00	\$2,500.00	\$600.00	\$600.00			\$1,000.00		\$250.00	
13	2573.502	CULVERT END CONTROLS	EACH	2	\$500.00	\$1,000.00	\$175.00	\$350.00	\$175.00	\$350.00	\$175.00	\$350.00	\$175.00	\$350.00
14	2573.503	SILT FENCE, TYPE MS	LF	1441	\$4.00	\$5,764.00	\$2.50	\$3,602.50	\$2.50	\$3,602.50	\$2.50	\$3,602.50	\$2.50	\$3,602.50
15	2573.503	FLOTATION SILT CURTAIN TYPE MOVING WATER (3 FT DEPTH)	LF	300	\$30.00	\$9,000.00	\$20.00	\$6,000.00	\$19.95	\$5,985.00	\$19.95	\$5,985.00	\$19.95	\$5,985.00
16	2573.503	SEDIMENT CONTROL LOG TYPE STRAW	LF	400	\$7.50	\$3,000.00	\$5.00	\$2,000.00	\$5.00	\$2,000.00	\$5.00	\$2,000.00	\$5.00	\$2,000.00
17	2575.501	TURF ESTABLISHMENT	LS	1	\$4,500.00	\$4,500.00	\$2,500.00	\$2,500.00	\$2,500.00	\$2,500.00	\$2,500.00	\$2,500.00	\$2,500.00	\$2,500.00
18	2575.504	EROSION CONTROL BLANKETS CATEGORY 3N	SY	2008	\$3.00	\$6,024.00	\$3.00	\$6,024.00	\$2.95	\$5,923.60	\$2.95	\$5,923.60	\$2.95	\$5,923.60
19	2575.523	RAPID STABILIZATION METHOD 3	MGAL	22	\$300.00	\$6,600.00	\$300.00	\$6,600.00	\$50.00	\$1,100.00	\$300.00	\$6,600.00	\$300.00	\$6,600.00
		Tota	l Non-Pai	rticipating:		\$101,165.00		\$129,814.50		\$157,117.10		\$120,661.62		\$133,722.10
Participat	ing					•	•		•	•		•	•	
20	2021.501	MOBILIZATION	LS	1	\$65,000.00	\$65,000.00	\$90,700.00	\$90,700.00	\$126,639.76	\$126,639.76	\$71,170.00	\$71,170.00	\$149,864.00	\$149,864.00
21	2401.503	TYPE S (TL-4) BARRIER CONC (3S52) (P)	LF	302	\$115.00	\$34,730.00	\$70.00	\$21,140.00	\$100.00	\$30,200.00	\$132.90	\$40,135.80	\$150.00	\$45,300.00
22	2401.507	STRUCTURAL CONCRETE (3B52) (P)	CY	83	\$950.00	\$78,850.00	\$1,100.00	\$91,300.00	\$800.00	\$66,400.00	\$1,387.82	\$115,189.06	\$975.00	\$80,925.00
23	2401.508	REINFORCEMENT BARS (EPOXY COATED) (P)	LB	108330	\$1.25	\$135,412.50	\$1.25	\$135,412.50	\$1.50	\$162,495.00	\$1.27	\$137,579.10	\$1.65	\$178,744.50
24	2401.601	STRUCTURE EXCAVATION	LS	1	\$7,500.00	\$7,500.00	\$6,000.00	\$6,000.00	\$9,000.00	\$9,000.00	\$20,000.00	\$20,000.00	\$15,000.00	\$15,000.00
25	2401.601	SLOPE PREPARATION	LS	1	\$7,500.00	\$7,500.00	\$10,000.00	\$10,000.00	\$5,500.00	\$5,500.00	\$10,000.00	\$10,000.00	\$15,000.00	\$15,000.00
26	2401.618	BRIDGE SLAB CONCRETE (3YHPC-M) (P)	S F	5285	\$52.50	\$277,462.50	\$48.00	\$253,680.00	\$54.00	\$285,390.00	\$56.83	\$300,346.55	\$64.00	\$338,240.00
27	2402.502	FLOOR DRAIN TYPE B702 MODIFIED	EACH	4	\$250.00	\$1,000.00	\$500.00	\$2,000.00	\$432.00	\$1,728.00	\$336.65	\$1,346.60	\$850.00	\$3,400.00
28	2402.508	STRUCTURAL STEEL (3306) (P)	LB	530	\$5.00	\$2,650.00	\$7.47	\$3,959.10	\$6.00	\$3,180.00	\$12.28	\$6,508.40	\$6.00	\$3,180.00
29	2451.607	STRUCTURAL BACKFILL (CV) (P)	CY	270	\$15.00	\$4,050.00	\$45.00	\$12,150.00	\$28.00	\$7,560.00	\$37.85	\$10,219.50	\$38.00	\$10,260.00
30		C-I-P CONC TEST PILE 100 FT LONG 12"	EACH	2	\$10,000.00	\$20,000.00	\$15,000.00	\$30,000.00			\$16,000.00		\$15,000.00	\$30,000.00
31	2452.502	C-I-P CONC TEST PILE 105 FT LONG 16"	EACH	2	\$12,500.00	\$25,000.00	\$25,000.00	\$50,000.00			\$32,000.00		\$23,000.00	\$46,000.00
32		PILE POINTS 12"	EACH	8	\$200.00	\$1,600.00	\$300.00	\$2,400.00			\$274.15			
33	2452.502	PILE POINTS 16"	EACH	12		\$3,600.00	\$425.00	\$5,100.00			\$376.25		\$430.00	
34		C-I-P CONCRETE PILING 12"	LF	540	\$45.00	\$24,300.00	\$38.00	\$20,520.00			\$56.42			
35		C-I-P CONCRETE PILING 16"	LF	950	\$55.00	· ·	\$62.00	\$58,900.00			\$65.45			

	Project: SAP 001-618-005 - Bridge Replacement over Willow River on CSAH 18			Engineers Est	ımate	Redstone Construction, LLC - Structural S Mora, MN Hutchinson		Structural Specialties Inc Hutchinson, MN		S & R Reinforcing, Inc Aitkin, MN		Robert R. Schroeder Construction, Inc Glenwood, MN	
Line No.	Item	Units	Quantity	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price	Unit Price	Total Price
36	2502.501 DRAINAGE SYSTEM TYPE (B910)	LS	1	\$1,500.00	\$1,500.00	\$2,800.00	\$2,800.00	\$1,650.00	\$1,650.00	\$2,000.00	\$2,000.00	\$2,500.00	\$2,500.00
37	2511.504 GEOTEXTILE FILTER TYPE 7	SY	660	\$4.50	\$2,970.00	\$3.75	\$2,475.00	\$3.00	\$1,980.00	\$3.00	\$1,980.00	\$4.00	\$2,640.00
38	2511.507 RANDOM RIPRAP CLASS III	CY	310	\$60.00	\$18,600.00	\$110.00	\$34,100.00	\$70.00	\$21,700.00	\$80.00	\$24,800.00	\$88.00	\$27,280.00
39	2563.601 TRAFFIC CONTROL	LS	1	\$6,500.00	\$6,500.00	\$4,200.00	\$4,200.00	\$7,500.00	\$7,500.00	\$4,600.00	\$4,600.00	\$4,000.00	\$4,000.00
40	2575.504 TURF REINFORCEMENT MAT CATEGORY 3	SY	263	\$12.50	\$3,287.50	\$16.50	\$4,339.50	\$16.50	\$4,339.50	\$16.50	\$4,339.50	\$16.50	\$4,339.50
		Total Par	rticipating:		\$773,762.50		\$841,176.10		\$865,182.26		\$945,567.01		\$1,069,403.00
	Total Non-Participating:				\$101,165.00		\$129,814.50		\$157,117.10		\$120,661.62		\$133,722.10
	Total Participating:				\$773,762.50		\$841,176.10		\$865,182.26		\$945,567.01		\$1,069,403.00
								r			1	1	
	Totals for Project SAP 001-618-005				\$874,927.50		\$970,990.60		\$1,022,299.36		\$1,066,228.63		\$1,203,125.10
	% of Estimate for Project SAP 001-618-005						10.98%		16.84%		21.86%		37.51%
	Tatala fan Canturat 20222				6074 027 50		¢070.000.50		64 022 206 26		¢4.000.222.02	1	64 202 425 42
	Totals for Contract 20222				\$874,927.50		\$970,990.60		\$1,022,299.36		\$1,066,228.63		\$1,203,125.10
	% of Estimate for Contract 20222						10.98%		16.84%		21.86%		37.51%

I hereby certify that this is an exact reproduction of bids received.

Certifie	d By:	License No.	24340
Date:	11-2-21		